Vidyasagar College for Women 39, Sankar Ghosh Lane Kolkata -700006

Tender Notice # VCFW/ Electrical Work of Point Wiring, New LED Down Light, Power Board, A.C. Line, at New Room of 2nd Floor (near staircase) under Vidyasagar College for Women/2023-24

Sealed quotations are invited from reputed/ enlisted vendor for Electrical Work of Point Wiring, New LED Down Light, Power Board, A.C. Line, at New Room of 2nd Floor (near staircase) under Vidyasagar College for Women/2023-24. Sealed quotation should be reached to the college office on or before 12/12/2023 between 8.00 am and 12.00 noon on working days only. Quotations should be in the name of "Principal, Vidyasagar College for Women, 39 Sankar Ghosh Lane, Kolkata — 700006". Mention the subject of your quotations as "Quotations for Server against the advertisement published in college website dated 04.12.2023 Details specification is given below.

SI.N o.	Description of Work	Uni	Qty	Amount
1	Distribution wiring in 2X22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unseathed copper wire (Brand approved by EIC) in 20 mm size PVC rigid conduit'FR' with 1X22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated &unsheathed copper wire for ECC, to light/fan/call bell points with Modular type switch board with top cover plate and earthing attachment fixed on wall incl. Mending good damages to original finish	No	03	
2	On Board	No	01	
3.	S & F of LED light fittings complete with all accessories & fixing devices as below: 1.CROMPOTON Cat no.: QUARTZ, LCDE-18-CDL/LSDE-18-CDL	pel S		
4.	Distribution wiring in 1.1 KV single core strander 'FR' PVC insulated & usheathed copper wire (Brand approved by EIC) in 20 mm size PVC rigid conduit 'FR' (Precision make) incl. necy. Fittings as required. Item No. 1 (a). P.E-14	15.13.400.		
	a)2X36/0.3 (2.5 sqrm)+ 1X22/0.3(1.5 sqrm) ECC	Mtr	40	
5.	Supply & Fixing 240 V, 4 nos. 10 A, 3 pin Modular type plug socket with 4 nos. 10A Modular type switch (Brand approved by EIC), without plug top on 6 Module GI Module type switch board with 6Module top cover plate flushd in wall incl. S& F switch board and cover plate and making necy. Connections with PVC Cu wire and earth continuity wire etc.	Set	03	
6.	Supply & Installation of Ac Line with 2X2.5 Sq.mm +1X1.5 Copper Wire & AC Starter Set (Starter + MCB +Socket) 6 Module Cover with Plate , (North-West)	No	01	

(Dr. Sutapa Ray) 04/12/2023 Principal

Principal
Vidyasagar College for Women
Kolkata