



**VIDYASAGAR COLLEGE FOR WOMEN**

**39, SANKAR GHOSE LANE, KOLKATA – 6**

**Tender Notice : VCFW/Renovation-Accounts Room/2024-25**

Sealed tenders are invited from Reputed/Enlisted Vender for "Renovation of font side of Accounts Room, Anti Chamber and Principal's Room at 1<sup>st</sup> floor of Vidyasagar College for Women (New Building)". Quotations should be addressed to 'The Principal, Vidyasagar College for Women, Kolkata – 700006'. Mention the subject of your quotations as "Renovation of font side of Accounts Room, Anti Chamber and Principal's Room at 1<sup>st</sup> floor of Vidyasagar College for Women (New Building) against the advertisement published in college website dated 04.11.2024".

The Tender paper shall be received between 8.00 AM and 01.0 PM within 10 days from the date of publication of this notice.

Work details is attached in this notice. Detail specifications of the work is also available from Head clerk, Vidyasagar College for Women.

Sutapa Ray

Dr. Sutapa Ray

04/11/24

Principal


Vidyasagar College for Women

Principal  
Vidyasagar College for Women  
Kolkata

## Specifications of the work

Work Name: Renovation of front side of Accounts Room, Anti Chamber and  
Principal's Room

Sl. No.	DESCRIPTION	QUANTITY	RATE (₹)	AMOUNT (₹)
1.	Laminate pasting on plywood surfaces with 12mm thick deluxe quality as per design to be shown matching with the colour shade including labour charges with all materials.	200 Sq.ft		
2.	Extra panelling work for hidden light at PR with 12mm ply duly laminated as approved.	50Sq.ft		
3.	Side Table (size: 6'-0" x 2'-6" x 2'-3" height) as per drawing, inside drawers, shutters, storage space etc with 19mm ply structure, 1 mm laminate finish, including all hardware required.	01 such		
4.	Group Discussion Table at PR SIZE: 8'-0" X 3'- 6"X2'-6" height as per drawing with 19mm/25mm top and sides and 1mm branded laminate finish.	01 such		
5.	Grill door covering at entry of Ac's Room with 12mm ply from both sides and laminate pasting including arrangement for door shutter with heavy lock and handle etc.	90 Sq.ft		
6.	Anti-chamber/ Ac's room False ceiling with gypsum grid ceiling with 600 x 600mm tiles of 12mm thick, Complete with all.	140 Sq.ft		
7.	Painting of walls, pilers, beams etc with necessary surfacing with liquid putty, one coat primer and 2 coats acrylic emulsion paint of approved brand and shade.	210 Sq.ft		
			<b>Rs</b>	
			GST( %)	
			Total	

  
 Dr. Sutapa Ray - 04/11/24

**Principal**  
**Vidyasagar College for Women**  
**Kolkata**