

Common Committee
Vidyasagar Group of Colleges
39, Sankar Ghosh Lane
Kolkata-700006

Painting & Repairing of Canteen of Vidyasagar Group Of Colleges

Tender No: VGC/PAINT & REPAIR/2025 -3

Date: 11.01.2025

Quotations are invited in sealed cover for the **Painting & Repairing of Canteen of Vidyasagar Group of Colleges** (old building) 39, Sankar Ghosh Lane Kolkata-700006 as per Annexure from established contractors with proven track record.

Vendors may visit the actual site during office hours i.e 11 am to 4p.m (Contact :9123318397)

Time limit of completion of the work **07 days** after issuing of work order.

Interested vendors are requested to submit tender in sealed envelope containing quotation, copy of trade license, GST registration certificate, PAN card and Credentials(if any) *addressing to the* Convener, Common Committee, Vidyasagar Group of Colleges. The Common Committee of Vidyasagar Group of Colleges will not be liable for late receiving of any quotation. The Common Committee of Vidyasagar Group of Colleges has a right to reject any quotation without assigning any reason and the decision will be binding all.

Important Notes:

1. Date of Publication of Tender : 11.01.2025
2. Time for Submission : 11.00 am to 4.00 pm (except Holidays)
3. Last date for submission : 17.01.2025 upto 2.00pm
4. Place of Submission : Tender box placed at the first floor in front of room no. 9 of Vidyasagar College (old building) 39, Sankar Ghosh Lane Kolkata-700006
5. Opening of Tender : 17.01.2025 at 2.15 pm

Sd/-
Convener
Common Committee
Vidyasagar Group of Colleges

Annexure

Painting & Repairing of Canteen of Vidyasagar Group Of Colleges			
	Approx Area (sq. Ft)	Rate (Rs.)	Amount (Rs.)
<p>Painting Details of Distemper painting works 1. Scrubbing of wall. 2. Filling the cracks by putty. 3. Using distemper paint on wall and ceiling surfaces (2 coats). 4. Cleaning of the floors. 5. Applying oil enamel paints on scarting PAINTS TO BE USED: Berger Acrylic Distemper /Asian Acrylic Distemper /Birla Acrylic Distemper</p>	2500		
<p>Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system (E-Grid T 2430/1510 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long and Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on the perimeter of the wall by steel screws with distance 300mm c/c. The Main Runners to be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at a regular interval of 600 mm to form a modular grid of 1200mm X 600mm. Additional Cross Tees of 600 mm shall be placed perpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. 4 mm thick High Pressure Steam Cured Non Asbestos pearl designer Fibre Cement Standard Ceiling Board (Density > 1500 Kg/m³) of size 595 mm X 595 mm, conforming IS 14862 & Type A Category IV of ISO 8336, tested as per AS-1530 part 3 & BS-476 Part 4,5,6,7 & 8, should be placed in the Grid module to form a False Ceiling. All complete as per the drawing & directions of Engineer-in-charge. a) False Ceiling (with 4mm thick Pearl Designer Fibre Cement Board and E-Grid</p>	150		
<p>Supplying and fixing of Vitrified matt finish floor tiles, over 20 mm (av.) thick base of Cement mortar (1:4) laid with white cement slurry.</p>	200		

Supplying, fitting and fixing 6 kg fire extinguisher (ABC type) Minimax or equivalent.	2 Nos		
SANITARY AND PLUMBING WORKS			
Total			

Sd/-
Convener
Common Committee
Vidyasagar Group of Colleges