

VIDYASAGAR COLLEGE FOR WOMEN
39, SANKAR GHOSE LANE, KOLKATA – 6
Tender Notice : EXT/VCFW/UNION-1/22

Sealed tenders are invited by the Principal of Vidyasagar College For Women, 39 Sankar Ghosh Lane, Kolkata – 6 from the bonafied Supplier for “Re-Construction of Union Room & Gym Room upto Plinth level at Vidyasagar College For Women.”. The Tender paper shall be received upto 11.00 A.M. on 27.07.2022.

Details specifications are available from Head clerk, Vidyasagar College for Women.

Sl. No.	Description of Items	Unit	Qnty.	Rate(Rs.)	Amount (Rs.)
1	DISMANTLING WORK				
1.1	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m.	Cu.M	12.00		
1.2	Dismantling R.C. floor, roof, beams etc. including cutting rods and removing rubbish as directed within a lead of 75 m. including stacking of steel bars.	Cu.M	12.00		
1.3	Removal of rubbish, earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge	Cum	50.00		
1.4	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (i) (a) Depth of excavation not exceeding 1,500 mm.	%Cum	40.00		
1.5	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation.	%Cum	12.00		

2	CIVIL WORK				
2.1	Controlled cement concrete with well graded stone chips (20 mm. nominal size) excluding shuttering and reinforcement with complete design of concrete as per ISI-456 and relevant special publications submission of job mix formula after preliminary mix design after testing of concrete cubes as per direction of Engineer-in-charge. Consumption of cement will not be less than 300kg of cement with Super plasticiser per cubic meter of controlled concrete but actual consumption will be determined on the basis of preliminary test & job-mix formula. In ground floor and foundation. [using concrete mixture] M 25 Grade. (i) Pakur Variety	Cum.	15.00		
2.2	Hire and labour charges for shuttering with centreing and necessary staging upto 4 m. using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels curved or straight including fitting, fixing and striking out after completion of works. (upto roof of ground floor) (a) 25 mm. to 30 mm. thick wooden shuttering as per decision & direction of Engineer-in-charge.	Sqm	92.00		
2.3	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. including supply of rods, initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every inter-section, complete as per drawing and direction. (a) For works in foundation, basement and upto roof of ground floor / upto 4m. (i) Tor steel/Mild steel	MT	3.40		
				TOTAL	
	GST @ 18%				
			Total:		

(Rupees)

Date:
Place:

Signature of the contractor
with Seal