


VIDYASAGAR COLLEGE FOR WOMEN

39, SANKAR GHOSH LANE , KOLKATA – 700006

TENDER NOTICE: VCFW/E.I. Work /Principal's Room/NB

Sealed tenders are invited from Reputed /Enlisted vender for EI work at Principal's Room, Vidyasagar College for Women (New Building). Quotation should reach college office within 7 days from the date of issuance of this notice between 8.00 AM and 12 noon (Working days only). Quotation should be in the name of "The Principal, Vidyasagar College for Women, Kolkata 700006". Mention the subject of your quotation as "Electrical Work at Principal's room, NB against the advertisement published in College website dated 20.09.24".

Details specification of the work is also available from Head Clerk, Vidyasagar College for Women.



DR. SUTAPA RAY **Principal**
Principal **Vidyasagar College for Women**
Kolkata
Vidyasagar College for Women

Date: 20.09.24

SPECIFICATION FOR TENDER NOTICE NUMBER

E.I. work of Point Wiring , New LED Down Light, Power Board , A.C. Line at Principal Room and Toilet, Vidyasagar College for Women, New Building

Sl. No	Description of Work	Unit	Quantity	Rate	Amount
1	Distribution wiring in 2x22/0.3(1.5 sq mm)single core standard 'FR' PVC insulated and unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR', with 1x22/0.3 (1.5 sq mm) single core stranded 'FR' PVC insulated and unsheathed cooper wire for ECC, to light / fan/ call bell points with modular type switch fixed on modular iron switch board with top cover plate and earthing attachment fixed on wall.	No	12		
2	On Board	No	02		
3	S & F of LED light fittings complete with all accessories & fixing devices as bellow :1.CROMPTON Cat No: QUARTZ LCDE-18-CDL/LSDE-18-CDL L.P. Rs.	Set	10		
	S & F of LED light fittings complete with all accessories & fixing devices as bellow :1.CROMPTON Cat No: QUARTZ LCDE-9-CDL/LSDE-9-CDL L.P. Rs.	Set	02		
4	Distribution wiring in 1.1 KV single core standard 'FR' PVC insulated and unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR', (Precision make)incl. necy. fittings as required. Item no. 1(a)P.E-14				
	(a)2x36/0.3 (2.5 sq mm) + 1x 22/0.3 (1.5 sq mm) ECC	Mtr.	50		
5	Supply & Fixing 240 v, 3 nos. 6A, 3 pin Modular type plug socket with 3 nos. 6A Modular type switch (Brand approved by EIC), 16A Modular switch type MCB (C-Curve) and Indicator without plug top on 12 Modular GI Modular type switch board with 12 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy.	No	06		
6	Supply & Installation of AC Line with 2x2.5 sq.mm. + 1x1.5				
	Total				
	GST				
	Grand Total				