



**VIDYASAGAR COLLEGE FOR WOMEN
39, SANKAR GHOSH LANE, KOLKATA – 6**

Tender Notice : VCFW/ HOSTEL/3RD-F/CON/1

Sealed tender are invited by the principle of Vidyasagar college for women, 39 Sankar Ghosh Lane , Kolkata – 6, from Reputed/Enlisted Vender for “**Construction of hostel rooms at 3rd floor of Vidyasagar Hostel for Women- Part - 1**”. The Tender paper shall be received at the college office, new building upto 12.00 Noon on 27.12.2021.

Specification of the work is enclosed herewith.

Sd/-

Dr. Rupali Chaudhuri

Principal

Vidyasagar College for Women

20.12.2021

"Construction of hostel rooms at 3rd floor in Vidyasagar Hostel for Women".

39, Sankar Ghosh Lane, Kolkata – 700 006

Sl. No.	Description of Items	Unit	Qty.	Rate(Rs.)	Amount (Rs.)
1	Dismantling terraced roof in ground floor roof (including floor finish, if any.) taking out carefully tiles with beams, joists, tees or burgahs covering floor below, sorting and stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m	Cu.M	13.50		
2	Removal of rubbish, earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge	Cum	40.00		
3	Labour for chipping of concrete surface before taking up plastering work.	Sqm	50.00		
4	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m.	Cu.M	10.00		
5	Controlled cement concrete with well graded stone chips (20 mm. nominal size) excluding shuttering and reinforcement with complete design of concrete as per ISI-456 and relevant special publications submission of job mix formula after preliminary mix design after testing of concrete cubes as per direction of Engineer-in-charge. Consumption of cement will not be less than 300kg of cement with Super plasticiser per cubic meter of controlled concrete but actual consumption will be determined on the basis of preliminary test & job-mix formula. In ground floor and foundation. [using concrete mixture] M 25 Grade. (i) Pakur Variety	Cum.	3.30		
6	Hire and labour charges for shuttering with centreing and necessary staging upto 4 m. using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels curved or straight including fitting, fixing and striking out after completion of works. (upto roof of ground floor) (a) 25 mm. to 30 mm. thick wooden shuttering as per decision & direction of Engineer-in-charge.	Sqm	42.00		

Sl. No.	Description of Items	Unit	Qty.	Rate(Rs.)	Amount (Rs.)
7	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. including supply of rods, initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every inter-section, complete as per drawing and direction.	MT	0.52		
8	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	Sqm	110.00		
9	Brick work with 1st class bricks in cement mortar (1:6).(a) In foundation and plinth.	Cum.	2.00		
10	Making one set of scaffolding only for replacing glass panels, painting, uprooting plant and another repairing works of building and S&P works for external works only with 10 cm. dia bamboo as main posts at the rate of 1 metre centre to centre and 7.5 cm. dia bamboo ties @ 0.75 metre apart fitting and fixing with necessary coir, nails etc. as per direction of the Engineer-in-charge.				
	a) 3.90 metre height	Each	17		
	b) Extra for additional 3.6 height or part thereof	Each	30		
11	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints, including throating, nosing and drip course, scaffolding/staging where necessary (Excluding cost of chipping over concrete surface)				
	(i) With 1:6 cement mortar (a) 20 mm. thick plaster	Sqm	130.00		
	(ii) With 1:4 cement mortar (b) 15 mm. thick plaster	Sqm	175.00		
12	Supplying, fitting and fixing M.S. clamp for fixing door and window frames made of flat bent bar, end bifurcated with necessary screws etc. in cement concrete (1:2:4) including cutting of brick work / concrete work as per direction. (Cost of concrete will be paid separately). (i) 40mm. X 6mm., 250mm. Length.	Each	12.00		

Sl. No.	Description of Items	Unit	Qty.	Rate(Rs.)	Amount (Rs.)
13	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame exluding cost of concrete, Iron Butt Hinges and M.S clamps. (The quantum should be correted upto three decimals). Sal : Malayasian	Cum	0.07		
				TOTAL	

(Rupees)

Date :
Place:

Signature of the contractor
with seal