

VIDYASAGAR COLLEGE FOR WOMEN
39 SANKAR GHOSH LANE
KOLKATA – 700 006

TENDER NOTICE: VCFW/Roof-Shed Civil Work/Extension/2024-25 dated
23.10.2024

Sealed quotations are invited from reputed/enlisted venders for “Roof shed & allied Civil Work at 3rd Floor of New Building, New Construction area, Vidyasagar College for Women”. Quotations should reach college office within 10 days from the date of issuance of this notice between 8.00 AM and 12 noon. Quotation should be in the name of “The Principal, Vidyasagar College for Women, Kolkata – 700 006”. Mention the subject of the quotation as “Roof shed & allied Civil Work at 3rd Floor of New Building, New Construction area, Vidyasagar College for Women, New Building, Vidyasagar College for Women against the advertisement published in college website dated 23.10.2024” at the top of the sealed envelope. Detail specification of the work is attached herewith.

Name of Work: Roof shed & allied Civil Work at 3rd Floor of New Building, New Construction area

| Sl. No. | DESCRIPTION | Quantity | Rate | Amount | |
|---------|--|------------|------|--------|----|
| | | | | Rs. | P. |
| 1 | Brickwork at pillars, with 1 st class bricks with 1: 6 cement: sand mortar (250mm thick) | 0.040 Cu m | | | |
| 2 | 125mm thick brick work with 1 class bricks in parafet Etc (1:4 cement mortar) | 08 Sq m | | | |
| 3 | Plaster to walls, column etc with 1:6 cement mortar 20mm thick | 20 Sq m | | | |
| 4 | Rendering the surfaces with white cement based wall putty (1.5mm thick) | 60 Sq m | | | |
| 5 | Applying interior grade acrylic primer on putty surfaces as per brand approved | 60 Sq m | | | |
| 6 | Applying interior acrylic emulsion paint of approved brand and shade on primer surface after necessary surface preparation (2 coats) | 60 Sq m | | | |
| 7 | Supply and laying true to line and level vitrified tiles size 600x 600x 10mm thick of approved brand and shade including backing materials as per instruction of EIC | 30 Sq m | | | |
| 8 | Supply and installation of False ceiling structure of gyproc ceiling sections, forming a grid of 600x600mm and placing E board of 595 x 595mm x 6mm thick. | 22 Sq m | | | |
| 9 | Supply and installation of wall paneling with 12.5mm ahick gyproc boards of SAINT GOBAIN make, stud & floor sections, including joining of boards with compound as per mfr's specification | 20 Sq m | | | |

| | | | | |
|----|--|-----------|--------------------|--|
| 10 | Aluminium window 2/3 track sliding with 1.5mm thick extruded sections of Jindal make, with 5mm clear glass, complete with all | 8 Sq m | | |
| 11 | M.S. structure in roof truss with rectangular M.S. sections connected to each other with brackets, gusset Clits etc.....for trusses spanning within 12 mtr | 0.50 MT | | |
| 12 | Supply and fitting of colour polyester coated zinc-alloy sheet roofing (JSW/ JINDAL including proper ridge of 0.45 mm thick | 35 Sq m | | |
| 13 | M.S. or W.I ornamental grill at windows, 16kg/sq m As per design approved, 10/12mm sq bars | 10 Sq m | | |
| 14 | Supply and installation of Aluminium door 2 leaf with Door sections, bottom ACP sheet, top with clear glass of 5mm thick | 2.20 Sq m | | |
| | | | Total | |
| | | | GST | |
| | | | Grand Total | |



Dr. Sutapa Ray
Principal
Vidyasagar College for Women
Date: 23.10.2024